

# **Huawei**

## **H12-425 Exam**

### **HCIP-Data Center Facility Deployment V1.0 Exam**

#### **Questions & Answers Demo**

## Version: 4.0

---

### Question: 1

---

Site selection is one challenge for the traditional data center

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

### Question: 2

---

Unpredictable business, expansion and difficult investment is one of the challenges facing the development of traditional data center business.

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

### Question: 3

---

Which system affects the PUE most in Data Center.

- A. Power Distribution system
- B. Cooling System
- C. N/A
- D. Lighting system

---

**Answer: B**

---

---

### Question: 4

---

Which one is the best PUE in the following:

- A. 1.06
- B. 2
- C. 0.3
- D. -0.5

---

**Answer: A**

---

[https://en.wikipedia.org/wiki/Power\\_usage\\_effectiveness](https://en.wikipedia.org/wiki/Power_usage_effectiveness)

---

**Question: 5**

---

Cold/Hot aisle containment is used to solve the problem of heat dissipation in Data Center.

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

**Question: 6**

---

Modular Data Center is on-demand deployment, which avoids over-investment.

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

**Question: 7**

---

Which Technologies or solutions can reduce PUE?

- A. Increasing the number of access control systems
- B. Efficient modular UPS
- C. Cold/hot aisle containment
- D. In-row cooling

---

**Answer: BCD**

---

---

**Question: 8**

---

FusionModule2000 is an outdoor smart modular data center solution.

- A. TRUE
- B. FALSE

---

**Answer: B**

---

FusionModule2000 is an indoor model

---

**Question: 9**

---

FusionModule1000 is an indoor prefabricated all in-one data center solution.

- A. TRUE
- B. FALSE

---

**Answer: B**

---

FusionModule1000A All-in-One Prefabricated Data Center is a green and reliable outdoor data center solution.

---

**Question: 10**

---

FusionModule1000A series solution meets the TIER 4 requirements if it adopts 2N power supply and distribution system.

- A. TRUE
- B. FALSE

---

**Answer: B**

---

(FM1000A does not support Tier 4)

---

**Question: 11**

---

Depending on different layouts, the batteries can be deployed inside or outside FusionModule2000

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

**Question: 12**

---

When ATS is in automatic mode, the handle for manual operation must be remove.

- A. TRUE
- B. FALSE

---

**Answer: A**

---

---

**Question: 13**

---

Smart Electricity meter of PDU8000 is abnormal, is it possible that:

- A. The transformation ratio of current or voltage is incorrectly set.
- B. Cables to the voltage collector are not properly connected.
- C. The current transformer is faulty.

D. The smart electricity is faulty.

---

**Answer: ABCD**

---

---

**Question: 14**

---

Which kind of start-up principle does gas fire extinguishing system have?

- A. Automatic startup
- B. Emergency startup
- C. Safe startup
- D. Manual startup

---

**Answer: ABD**

---

**Thank You For Trying H12-425 PDF Demo**

**To try our H12-425 Premium Files visit link below:**

**<https://examsland.com/latest-exam-questions/H12-425/>**

**Start Your H12-425 Preparation**

**Use Coupon **EL25** for extra 25% discount on the purchase of Practice Test Software.**